deputed by him in this behalf at Chitaldrug, on the 7th day of December 1929, as the original Lessees failed to pay up the first instalment due on 1st November 1929.

District	Taluk	Hobli	Remarks
Chitaldrug...	Chitaldrug ...	Bharmasagara... ...	Includes produce on all Government unoccupied lands, Amrut Mahal Kavals, Plantations, and State Forests and excludes the produce of Inam, Jodi, Kayamgutta, Sarvamanya, Kandayam and other lands which are in the occupancy of private Individuals. Removal of Kakke bark in plantations is prohibited. The sale will be held in the District Forest Office, Chitaldrug.
	Molakalmuru ...	Devasamudra	
	Chitaldrug ...	Chitaldrug	
		Guntanur	
		Thurvanur	
	Challakere ...	Parasurampur ...	
		Naikanhatti	
	Jagalur ...	Whole Taluk ...	
	Holalkere ...	Do	
	Davangere ...	Do	
	Harihar ...	Whole Sub-Taluk ...	
	Hosdurga ...	Srirampur Hobli ...	
		Madadagere	
	Hiriyur ...	Hiriyur	
		Javagondanhalli ...	
		Dharmapur	
		Imangala	

N.B.—For further particulars please see *Mysore Gazette*, pages 353 and 359, Part VI dated 2nd May 1929.

K. R. VENKATA RAO,
District Forest Officer.

ENGINEERING DEPARTMENT.

WATER SUPPLY DIVISION, BANGALORE.

Abstract Notification, dated 11th November 1929.

The attention of the public is invited to the notification calling for sealed tenders for improving water supply to Chamarajpet, Arlepet, Gowdenpet and certain other localities in Bangalore City published on pages 1324 and 1325, of Part VI of the *Mysore Gazette*, dated 14th November 1929.

The last date for the receipt of the tender is 23rd November 1929.

B. R. GARUDACHAR,
Executive Engineer.

KOLAR DIVISION.

Dated 12th November 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 9th December 1929, for constructing a Road Dam at 6—1 of Mulbagal-Punganur Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of (Rs. 150) one hundred and fifty in cash or Government Promissory Notes as earnest money and be superscribed "Tender for constructing a Road Dam at 6—1 of Mulbagal-Punganur Road," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenders must quote specific rates for all items both in words and figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimates will not be accepted.

Abstract estimate for constructing a Road Dam at 6—1 of Mulbagal-Punganur Road.

Serial No.	Items of work	Unit	Quantities
1	Earthwork excavating foundation including approach cutting on both sides and forming the same on river banks.	C.yds.	1,505
2	Concrete in surki mortar	C.ft.	2,412
3	Burnt stone in surki mortar	,,	2,700
4	Burnt stone sujicut apron	C.yd.	147
5	Jelly filling under apron	,,	96
6	Rough stone revetment to sides of approach and river bank...	,,	69
7	Burnt stone slabs 6" thick dressed	S.ft.	1,068
8	Metalling the approach with burnt metal including collection of metal and gravel with a lead of 1 mile per metal and ½ a mile for gravel and consolidation complete.	C.yd.	61
9	Baling water	Lump	sum
10	Unforeseen charges	Lump	sum

Dated 11th November 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 9th December 1929, for restoring Kendanahally addakunte R. No. 429—452 Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

4. Each tender must be accompanied by a deposit of (Rs. 300) three hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Kendanahally Addakunte Tank R. No. 429-452 Chintamani Taluk in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenders must quote specific rates for all items both in words and in figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate of quantities of work for Restoring Kendanahalli Addakunte Tank R. No. 429—452 of Chintamani Taluk.

Sl. No.	Items of work	Unit	Approximate quantities
	Bund R. L. 55·00.		
1	Earthwork to bund including watering and tamping ...	C.yds.	6,274
2*a*	Clearing loose earth and cutting steps and removing debris, etc.	Lump sum	
b	Excavating formation for puddle wall	C.yds.	12
c	Filling formation with selected earth for puddle ...	,,	44
3	Turfing to bund	S.yds.	4,587
4	Removing and resetting old stones available	C.yds.	510
5	New stone work	,,	1,094
6	Providing and fixing B. M. stones with chiselling figures, painting etc., complete.	No.	2
7	Do do grade stones ...	,,	25
8	Do do index stones ...	,,	25
9	Do do gauge stone ...	,,	1
10	Do do R. No. and Date stone ...	,,	1
11	Cutting Trenches removing prickly pears anthills, etc. ...	Grades	20
	Sluice at R. L. 46·00.		
1	Dismantling and removing debris of old sluice ...	Lump sum	
2	Earthwork excavation	C.yds.	228
2*a*	Refilling sluice gap with watering and tamping ...	,,	228
3	Concrete in surki mortar	C.ft.	203
4	Burnt brick in surki mortar	,,	513
5	Burnt stone slabs 6″ thick	Sq.ft.	201
6	Plastering with surki mortar	S.qr.	6·20
7	Providing plug and rod and locking arrangements ..	Lump sum	
8	Cutting grooves in orifice slabs	No.	3
	Constructing a weir at R. L. 50·00		
1	Earthwork excavation and using the earth to Tank bund ...	C.yd.	56
2	Concrete in surki mortar	C.ft.	382
3	Burnt brick in surki mortar	,,	1,244
4	Burnt stone slabs 6″ thick	S.ft.	585
5	Plastering with surki mortar	S.qr.	16·5
6	Rough stone work new	C.yds.	204
7	Earthwork to wing	,,	204

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE RAILWAYS.

Abstract Notification dated 16th November 1929.

Attention of the intending contractors is hereby invited to the notice calling for tenders for "collecting and stacking broken stone ballast on Mysore-Arsikere Railway," published in pages 1274, and 1275 Part VI of the *Mysore Gazette*, dated 7th November 1929.

Tenders will be received any working day up to 2 P.M., on 25th November 1929.

M. RAMAIYA,
Executive Engineer,
Mysore Railways, Hassan.